



PRE FABRICATED PANELS

# Prefabrication

- ▶ Prefabrication is the practice of assembling components of a structure in a factory or other manufacturing site, and transporting complete assemblies or sub-assemblies to the construction site





# Components of prefabricated structures

- Floors and Roofing slabs
  - Beams
  - Columns
  - Wall panels
  - Staircase
  - Lintels
  - Sunshades/Chajja projections
- 





#### QUAD-DECK PITCHED ROOF SHORING

| Panel Thickness | Quad-Deck Floor Weight (lb/ft <sup>2</sup> ) |      |      |      |      |      |      |
|-----------------|--|------|------|------|------|------|------|
|                 | 2"   | 3.5" | 5"   | 6.5" | 8"   | 9.5" | 11"  |
| 2"              | 45.1   | 31.4 | 27.5 | 43.5 | 33.1 | 34.4 | 46.9 |
| 3.5"            | 47.9   | 33.0 | 29.2 | 45.1 | 34.7 | 36.0 | 48.5 |
| 5"              | 49.5   | 34.6 | 30.8 | 46.7 | 36.3 | 37.6 | 50.1 |
| 6.5"            | 51.1   | 36.2 | 32.4 | 48.3 | 37.9 | 39.2 | 51.7 |
| 8"              | 52.7   | 37.8 | 34.0 | 49.9 | 39.5 | 40.8 | 53.3 |
| 9.5"            | 54.3   | 39.4 | 35.6 | 51.5 | 41.1 | 42.4 | 54.9 |
| 11"             | 55.9   | 41.0 | 37.2 | 53.1 | 42.7 | 44.0 | 56.5 |

Notes: These are minimum weights. Design with local loads & local conditions (snow, Super Deck, etc.) as applicable.



Screw through 4x4 beams into Quad-Deck metal decking steps spaced @ 12" o/c

Secure 4x4 beams to shoring beam nails prior to placing on the Quad-Deck Panels

**Notes:**  
 6'-0" max. o/c spacing between shoring beams  
 6" maximum distance between wall and shoring beam  
 Pour concrete @ 3" slump  
 Maximum Quad-Deck pitch recommended 12x12






**BEAM:** BEAM is a horizontal structural member, a long piece of timber or metal used to support the roof or floor of a building. It transfer the load on column. Example : Purlin , girder etc.

OR

A beam is a structural element that is capable of withstanding load primarily by resisting against bending.

#### TYPES OF BEAM:

1. RECTANGULAR BEAM
2. L SHAPED BEAM
3. INVERTED TEE BEAM
4. AASHTO BEAM


















# STANDARDIZATION

- ▶ It may be a national scale, obligatory over the whole country provided that the competent authorities publish catalogues of standard prefabricates and standard housing units or even whole buildings
- 





# LARGE PANEL WALL SYSTEM

Structural scheme with precast large wall panels can be classified as

- ▶ Cross wall system

  - The **cross walls are load bearing** walls

  - The façade walls are non load bearing

  - This system is suitable for high rise buildings

- ▶ Longitudinal wall system

  - The **Cross walls are non load bearing**

  - Longitudinal walls are load bearing

  - This system suitable for low rise buildings







Prefabricated panels serves two functions

- Stability (carries structural loads)
- As good partitions (infill wall panels)


**Infill panels**, also known as **infill** walls, are non-load-bearing **panels** that are installed between the floors of a building's primary structural frame

### **Principle Methods of prefabrications**

- Plant prefabrication
- Site Prefabrication



# MANUFACTURING PROCESS



- Preparation of moulds
  - Reinforcing and prestressing the components
  - Concreting the components
  - Hardening of the concrete
  - Demoulding the components and storage
- 




Prestressed concrete is a form of concrete used in construction. It is substantially "prestressed" during production, in a manner that strengthens it against tensile forces which will exist when in service



## Cantilever wall




## Gravity wall



### 3. Slab-to-Beam connection:

1. Hollow core slabs are set on bearing pads on precast beams.
2. Steel reinforcing bars are inserted into the slab keyways to span the joint.
3. The joint is grouted solid.
4. The slab may remain on topped with several inches of cast in place concrete.








# ADVANTAGES

- ▶ High quality product
- ▶ Decorative and good finishing
- ▶ Labour related savings
- ▶ Savings in time
- ▶ Overall efficiency is greatly increased
- ▶ Mass production is easier and quick
- ▶ Protected and controlled production environment
- ▶ Lower production costs and other cost savings
- ▶ Independence of climatic conditions
- ▶ The disruption of traffic is avoided
- ▶ Saves time and energy
- ▶ Formworks are reduced
- ▶ Earthquake resistance, more secure and safety



# Characteristics to be considered:

- 
- Easy availability
  - Light weight for easy handling and transport
  - Thermal insulation property
  - Easy workability
  - Durability in all weather condition
  - Non combustibility
  - Economy in cost
  - Sound insulation



# DISADVANTAGES

- ▶ Careful handling and high skilled supervision needed
  - ▶ Attention to be paid to the strength and corrosion resistance of joining of prefabricated sections
  - ▶ Similarly leaks can form at the joints
  - ▶ Transportation costs may be higher
  - ▶ Large prefabricated section require heavy duty cranes and precision measurements
  - ▶ Initial cost is high
- 